

अनुरक्षण एव आभियात्रिकी इकाई
MAINTENANCE & ENGINEERING UNIT
भाकअनुप-भारतीय कृषि अनुसंधान संस्थान
ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE
नई दिल्ली -१२
NEW DELHI-12

No. JK-105/19-12/ME Unit

Date: 31-05-2019

QUOTATION NOTICE

Item/percentage rate sealed Quotation are hereby invited on behalf of the Director, IARI from the Contractors Registered with CPWD, MES, Railways, MCD, PWD or other Central/State Govt./Semi Govt. agencies. The contractor must have valid IT-PAN,VAT,TIN and service tax registration number and having experience of two similar nature of works in last two years for the work mentioned below :

S.N	Name of work	Estimated cost / Item Rate	Earnest Money
1.	P/f false ceiling in the corridor near room no.229 second floor in the Division of NRCPB, LBS Building at IARI PUSA New Delhi-110012.	Rs. 1,70,535.00	Rs. 3500.00

Last date for receipt of applications for sale of quotation : 17.06.2019

Submission of quotation : up to 14:30 hours of 18.06.2019

Opening of quotation : 15:00 hours of 18.06.2019

Desirous and eligible agencies to download the schedule and details may visit IARI website www.iari.res.in or <http://eprocure.gov.in> and deposit the fee of Rs. 150/- (non-refundable) along with requisite EMD at the time of filing of Quotation. The rates on schedule and requisite eligibility documents should be filed in a separate envelopes submitted both together in a bigger envelope in case the Quotation is downloaded from the net, else the Quotation will be rejected. The schedule of work can also be purchased on payment of Rs. 150/- (non-refundable) from Tender Cell of M.E.Unit, Directorate during office hours on any working day by producing the eligibility documents and depositing the earnest money in the form of PO/DD favoring "Director, IARI, New Delhi-12." The Director IARI reserves the right to reject or accept any Quotation without assigning any reason. Quotations shall be submitted along with forwarding letter addressed to Director IARI otherwise quotation will not be considered.

Asstt. Admn. Officer (Works)

Copy to:-

1. Comptroller Directorate for kind information please.
2. F. & A.O.(Audit-IV)
3. AAO (Contingency).
4. In-charge USI to display on website.(The Quotation Notice already sent to IARI web master)

P/f false ceiling in the corridor near room no.229 second floor in the Division of NRCPB, LBS Building at IARI PUSA New Delhi-110012.

S.No	item no.	Particular	Qty.	Unit	Rate	Amount
1	12.52	Providing and fixing tiled false ceiling of approved materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.				
		12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm, made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part I and laminated with white 0.16mm thick fire retardant PVC film on the face side and 12micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit.	150.0	Sqm	1136.9	170535
TOTAL						170535

Subject to be following terms & conditions:-

1. The work shall be executed as per CPWD specifications.
2. Income Tax, work Tax & work cess as per norms shall be recovered from the bill.
3. 1% water and electrical charges will be recovered from the bill if supplied by the Department.
4. The work shall start within 2 days from the date of award and complete within one month failing which a penalty @ 1% per day delay will be imposed on the bill amount maximum upto 10%.
5. All the materials, laboures, T&P etc. required will be arranged by the firms itself.
7. Other item to be required at site to complete the work will be executed as per the lowest quoted rates on DSR-2016.
8. The rates shall remain valid for 90 days from the date of opening of quotations/tenders.
9. A running payment may be made of athe successful completion of work for 1/2nd or more amount of work.
10. The Director, IARI has the right to reject any or all the quotation/tenders without assigning any reason.
11. GST will be paid extra as per norms of the Ministry of Finance.

Percentage rate to be quoted above or below in figure on 'A' above:.....

In words:.....

I/c (MEU & W)

J.E.(C)