

रख-रखाव ँव अभियांत्रिकी इकाई  
भारतीय कृषि अनुसंधान परिषद  
भारतीय कृषि अनुसंधान संस्थान  
नई दिल्ली-12.

सं० 08-62/18-19/एमईयू

दिनांक 19.09.2018

निविदा सूचना

निदेशव, भा० कृ० अनु० सं०, की और से ँवद्वारा अधोलिखित निविदा कार्य हेतु के० लो० नि० वी०, एम० ई० एस०, रेलवेज, एम० सी० डी०, लोनिवी, या अन्य केंद्र / राज्य सरकार विभाग/ अर्द्ध सरकारी एजेंसीयो के साथ पंजीकृत पाल ठेकेदारो / एजेंसीयो व विशेषकृत एजेंसीयो से मुहरबंद मद दर निविदा आमंत्रित की जाती है । एजेंसीयो के पास वैध पैन, वैट/ टिन तथा सेवा कर पंजीकरण सं० होना अनिवार्य है । तथा नीचे निर्देशित कार्यों हेतु विगत दो वर्षों में दो समान कार्यों का अनुभव होना चाहिये ।

क्र० सं०	कार्य का नाम	अनुमानित लागत	धरोहर राशि
1.	Repair & renovation of room in the division of SS&AC at IARI PUSA, New Delhi.-110012.	Rs.102359 .00	Rs. 2500.00

निविदा की बिक्री हेतु आवेदन पत्र की प्राप्ति की अंतिम तिथि : 11.10.2018  
निविदा की प्रस्तुति की अंतिम तिथि : 12.10.2018 14.30  
निविदा खुलेगी : 12.10.2018 15.00  
निविदा की कीमत : रू० 150/- मात्र (अप्रतिदेय)

इच्छुक ँव पाल एजेंसीया अनुसूची को भा० कृ० अनु० सं० की वेबसाइट [www.iari.res.in](http://www.iari.res.in) और <http://eprocuře.gov.in> से विवरण को देखा तथा डाउन  
-रखाव ँव अभियांत्रिकी इकाई, निदेशालय, ' , नई दिल्ली-12 रू० 150/- मात्र (अप्रतिदेय) के भुगतान पर निविदा दस्तावेज क्रय

सहायक प्रशासनिक आधिकारी (निर्माण/ एम० ई० यूनिट )

MAINTENANCE & ENGINEERING UNIT  
ICAR-INDIAN AGRICULTURAL RESEARCH INSTITUTE  
NEW DELHI-12.

No. 08-62/18-19/ME Unit

Date: 19.09.2018

**QUOTATION NOTICE**

Item/percentage rate sealed Quotation are hereby invited on behalf of the Director, IARI from the Contractors Registered with CPWD, MES, Railways, MCD, PWD or other Central/State Govt./Semi Govt. agencies. The contractor must have valid IT-PAN, VAT, TIN and service tax registration number and having experience of two similar nature of works in last two years for the work mentioned below :

S.N	Name of work	Estimated cost / Item Rate	Earnest Money
1.	Repair & renovation of room in the division of SS&AC at IARI PUSA, New Delhi.-110012.	Rs.102359 .00	Rs. 2500.00

**Last date for receipt of applications for sale of quotation** : 11.10.18  
**Submission of quotation** : up to 14:30 hours of 12.10.18  
**Opening of quotation** : 15:00 hours of 12.10.18

Desirous and eligible agencies to download the schedule and details may visit IARI website [www.iari.res.in](http://www.iari.res.in) or <http://eprocure.gov.in> and deposit the fee of **Rs. 150/-** (non-refundable) along with requisite EMD at the time of filing of Quotation. The rates on schedule and requisite eligibility documents should be filed in a separate envelopes submitted both together in a bigger envelope in case the Quotation is downloaded from the net, else the Quotation will be rejected. The schedule of work can also be purchased on payment of **Rs. 150/-** (non-refundable) from Tender Cell of M.E.Unit, Directorate during office hours on any working day by producing the eligibility documents and depositing the earnest money in the form of PO/DD favoring "Director, IARI, New Delhi-12." The Director IARI reserves the right to reject or accept any Quotation without assigning any reason. Quotations shall be submitted along with forwarding letter addressed to Director IARI otherwise quotation will not be considered.

**Asstt. Admn. Officer (Works)**

Copy to:-

1. Comptroller Directorate for kind information please.
2. F. & A.O.(Audit-IV)
3. AAO (Contingency).
4. In-charge USI to display on website.(The Quotation Notice already sent to IARI web master)

## Repair &amp; renovation of room in the division of SS&amp;AC at IARI PUSA, New Delhi.-110012.

S.No.	Particular	Qty	Unit	Rate	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	60.00	sqm	22.40	1344
2	Providing and fixing 1st quality ceramic glazed Digital wall tiles of size 300 mm x 600 mm of Digital type conforming to IS : 15622 (thickness to be specified by the manufacture ) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	25.00	sqm	1216.40	30410
3	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete.				
	Size of Tile 600x600 mm	30.00	sqm	1119.40	33582
4	Providing and fixing tiled false ceiling of approved materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections ( galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.				
	12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm, made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part I and laminated with white 0.16mm thick fire retardant PVC film on, the face side and 12micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit.	30.00	sqm	993.15	29795

5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	30.00	sqm	87.35	2621
6	Distemping with 1st quality acrylic distemper (ready mixed) of approved manufacturer, of required shade and colour complete, as per manufacturer's specification.				
	Two or more coats on new work	30.00	sqm	53.15	1595
7	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :				
	One or more coats on old work	10.00	sqm	51.30	513
8	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by truck of 8.5cum capacity, including loading, transporting, unloading to approved municipal dumping ground or approved by Engineer-in-charge.	1.00	per trip	2500.00	2500
<b>TOTAL</b>				<b>102359</b>	

Subject to be following terms & conditions:-

1. The work shall be executed as per CPWD specifications.
2. Income Tax, work Tax & work cess as per norms shall be recovered from the bill.
3. 1% water and electrical charges will be recovered from the bill if supplied by the Department.
4. The work shall start within 7 days from the date of award and complete within one months failing which a penalty @ 1% per day delay will be imposed on the bill amount maximum upto 10%.
5. GST will be paid extra as per the norms of ministry of finance.
6. All the materials, laboures, T&P etc. required will be arranged by the firms itself.
7. The agency shall deposit security @ 5% of the sanctioned amount including EMD.
8. Any other item to be required at site to complete the work will be executed as per the lowest quoted rates on DSR-2016.
9. The rates shall remain valid for 180 days from the date of opening of quotations/tenders.
10. A running payment may be made of at the successful completion of work for 1/2nd or more amount of work.
11. The Director, IARI has the right to reject any or all the quotation/tenders without assigning any reason.

Percentage rate to be quoted above or below in figure on 'A' above:.....

In words:.....

Name with stamp & Signature of the Agency:.....

I/C (W)

T.A.(C)